INTERNATIONAL JOURNAL OF ENGINEERING MANAGEMENT AND SOCIAL SCIENCES (IJEMSS)

e-ISSN : 3139-065X

www.ijemss.com

editor@ijemss.com

Vol. 01, Issue 5, May 2026, pp : 73-85

Sustainable Road Infrastructure through Plastic Waste Utilization: Technologies, Benefits, and Challenges

[1]P Abhilash,

[1]Scientist,CSMRS,New Delhi,ORCID: **0000-0002-3767-7846**

ABSTRACT

The rapid increase in plastic waste generation has emerged as one of the most critical environmental challenges worldwide. Approximately 400 million tonnes of plastic waste are produced annually, with only a small percentage being effectively recycled, while the remainder accumulates in landfills, water bodies, and terrestrial ecosystems. Simultaneously, the road construction industry consumes substantial quantities of natural aggregates and bitumen, contributing to resource depletion and environmental degradation. The utilization of plastic waste in road construction has gained significant attention as an innovative and sustainable solution that addresses both waste management and infrastructure development challenges. This review article examines the application of waste plastics in bituminous road construction, focusing on material characteristics, processing techniques, engineering performance, environmental implications, and implementation practices.

Keywords: plastic waste roads, bituminous concrete, polymer modified bitumen, Marshall stability, rutting resistance, dry process, wet process, LDPE, PET, polypropylene, MoRTH circular, sustainable pavements, microplastics

1. Introduction

The study discusses various categories of plastic waste suitable for road applications, including polyethylene, polypropylene, polystyrene, and polyethylene terephthalate, along with their collection, segregation, shredding, and pre-treatment requirements. The two primary incorporation techniques, namely the dry process and wet process, are comprehensively analyzed. The influence of plastic modification on the physical, chemical, and rheological properties of bitumen is evaluated with reference to penetration value, softening point, viscosity, ductility, and temperature susceptibility. Furthermore, the article reviews the impact of plastic-modified bituminous mixtures on key pavement performance indicators such as Marshall stability, indirect tensile strength, rutting resistance, fatigue performance, skid resistance, and moisture susceptibility.

Comparative analyses from published experimental studies indicate that optimum plastic content generally enhances pavement durability, stiffness, and resistance to deformation while reducing maintenance requirements. The review also examines national and international case studies, including successful implementations in India, the Netherlands, Australia, and South Africa. Particular attention is given to India's Ministry of Road Transport and Highways guidelines promoting the mandatory utilization of waste plastics in road construction. Environmental concerns related to toxic emissions, microplastic generation, and long-term ecological impacts are critically discussed alongside life cycle assessment perspectives.

The article concludes that plastic waste utilization in road construction represents a promising pathway toward sustainable infrastructure and circular economy practices. However, challenges related to standardization, large-scale implementation, quality control, and environmental safety require further investigation. Future research directions emphasizing advanced characterization techniques, long-term field performance monitoring, and environmentally responsible practices are recommended to support wider adoption of plastic-modified pavements.

INTERNATIONAL JOURNAL OF ENGINEERING MANAGEMENT AND SOCIAL SCIENCES (IJEMSS)

e-ISSN : 3139-065X

www.ijemss.com

editor@ijemss.com

Vol. 01, Issue 5, May 2026, pp : 73-85

Plastic waste incorporation in bituminous road construction addresses both crises simultaneously. Polymers — whether blended with bitumen in the wet process or coated onto aggregates in the dry process — modify the rheological properties of bitumen, increasing its viscosity at high service temperatures, improving resistance to rutting and deformation, and potentially enhancing durability under traffic loading. At the same time, the use of non-recyclable waste plastic as a road construction material diverts it from landfill, reduces the volume of virgin bitumen required, and provides an economically attractive outlet for waste plastic that would otherwise have no value chain.

India has been a global pioneer in plastic road technology. The method developed by Professor Rajagopalan Vasudevan of Thiagarajar College of Engineering in Madurai, Tamil Nadu — which coats shredded waste plastic over heated aggregate before mixing with bitumen — has been implemented on thousands of kilometres of roads across India and has been recognised and mandated by the Ministry of Road Transport and Highways. This article reviews the technical, environmental, regulatory, and practical dimensions of plastic waste utilization in road construction comprehensively, drawing on the global research literature and Indian field experience.

2. Types of Plastic Waste Suitable for Road Construction

2.1 Polyethylene (LDPE, HDPE, LLDPE)

Low-density polyethylene (LDPE) is the plastic type most extensively studied and used in road construction applications in India and globally. It constitutes a major fraction of post-consumer waste plastic in the form of carry bags, packaging films, and flexible sachets — the category of plastic most commonly found littering streets, drains, and water bodies in Indian cities. LDPE has a melting point of 105 to 115 degrees Celsius and a softening point of 70 to 90 degrees Celsius, making it compatible with the temperature range of conventional bituminous mix production (150 to 180 degrees Celsius) without thermal degradation.

LDPE-modified bitumen consistently shows increased softening point, reduced penetration (indicating increased stiffness), and improved elastic recovery compared to unmodified bitumen. The polymer chains of LDPE interpenetrate the bitumen matrix at mixing temperatures, creating a network that restricts the flow of bitumen under load at elevated temperatures. The resulting modification is more pronounced than equivalent additions of HDPE (high-density polyethylene), whose higher crystallinity and stiffness reduce its compatibility with bitumen at conventional mixing temperatures, though HDPE offers greater high-temperature stability when properly incorporated.

2.2 Polypropylene (PP)

Polypropylene constitutes a significant fraction of municipal plastic waste in the form of woven sacks, food containers, caps, and straws. Its higher melting point (160 to 170 degrees Celsius) and stiffness compared to polyethylene make it particularly effective as a bitumen modifier for high-temperature performance improvement. PP addition at 4 to 8 percent by weight of bitumen has demonstrated increases in softening point of 8 to 18 degrees Celsius and reductions in penetration of 20 to 40 percent in multiple studies, indicating substantially improved resistance to high-temperature deformation.

The primary challenge of PP modification is its tendency toward phase separation — the polymer and bitumen forming two distinct phases rather than a homogeneous blend — particularly at low mixing temperatures or in the absence of compatibilizers. Careful control of mixing temperature (above 170 degrees Celsius), mixing

INTERNATIONAL JOURNAL OF ENGINEERING MANAGEMENT AND SOCIAL SCIENCES (IJEMSS)

e-ISSN : 3139-065X

www.ijemss.com

editor@ijemss.com

Vol. 01, Issue 5, May 2026, pp : 73-85

intensity, and cooling rate is required to achieve stable, homogeneous PP-bitumen blends that do not segregate during transport and placement. Blending PP with LDPE in ratios of 1:2 to 1:3 has been shown to improve blend compatibility and achieve superior combined performance compared to either polymer alone.

2.3 Polyethylene Terephthalate (PET)

PET, the plastic of carbonated beverage bottles, water bottles, and food containers, is among the most widely collected and sorted plastic waste fractions due to its relatively high and consistent recycling value. However, the quality of post-consumer PET is variable, and low-grade PET contaminated with labels, caps, or food residues is difficult to incorporate in conventional bottle-to-bottle recycling chains. This low-grade PET represents a significant potential feedstock for road construction applications.

PET has a high melting point of approximately 250 degrees Celsius, substantially above the mixing temperatures used in conventional bituminous concrete production. Direct blending of PET with bitumen at conventional temperatures therefore produces incomplete melting and a heterogeneous blend. Research approaches to incorporating PET in bituminous mixes include: use as aggregate replacement in the form of crushed PET crumb partially substituting fine aggregate (up to 10 percent substitution without significant strength loss); pyrolysis of PET to produce an oil fraction compatible with bitumen; and hot-coated aggregate processes in which PET is applied at temperatures sufficient for partial melting and adhesion to aggregate surfaces before bitumen addition.

2.4 Polystyrene (PS) and Mixed Plastics

Expanded polystyrene (EPS) — the white foam used in packaging, cups, and insulation — presents particular environmental problems due to its low density, resistance to compression, and tendency to fragment into small beads that persist in aquatic environments. Its high compatibility with aromatic solvents means that EPS dissolves readily in bitumen at mixing temperatures, producing a homogeneous blend that modifies bitumen properties in a manner similar to LDPE. Research has shown that 3 to 5 percent EPS addition increases softening point by 6 to 12 degrees Celsius and improves Marshall stability by 15 to 25 percent.

Mixed and unsorted plastic waste — the heterogeneous mix of plastic types found in municipal solid waste that is neither sorted for recycling nor segregated by type — is the most challenging but potentially the highest-volume feedstock for road construction applications. The variable composition of mixed plastic waste introduces inconsistency in bitumen modification properties and raises concerns about potentially harmful by-products from the thermal processing of PVC or chlorinated plastics. The pre-processing and quality control requirements for mixed plastic feedstocks are more demanding than for single-type plastics, and most established plastic road programs specify the plastic types acceptable for use.

3. Pre-Processing of Plastic Waste

Before incorporation in bituminous mixes, plastic waste must be subjected to pre-processing operations that transform heterogeneous, contaminated, and irregularly shaped waste into a consistent, clean, and appropriately sized feedstock. The pre-processing sequence typically comprises collection and segregation, washing and drying, shredding or granulation, and quality verification.

Washing and drying are essential to remove food contamination, soil, moisture, and residual chemicals that could compromise bitumen quality or produce harmful emissions during high-temperature mixing. Moisture

INTERNATIONAL JOURNAL OF ENGINEERING MANAGEMENT AND SOCIAL SCIENCES (IJEMSS)

e-ISSN : 3139-065X

www.ijemss.com

editor@ijemss.com

Vol. 01, Issue 5, May 2026, pp : 73-85

content must be below 0.5 percent before incorporation, as free water vaporizes explosively at bituminous mixing temperatures, creating dangerous pressure build-up and compromising mix homogeneity. Shredding or granulation reduces plastic waste to particle sizes of 2 to 4 mm for the dry process — small enough to coat aggregate particles uniformly but large enough to handle without dust generation — or to finer sizes for wet process blending with bitumen.

The removal of PVC (polyvinyl chloride) is a critical pre-processing requirement. PVC constitutes 2 to 4 percent of typical municipal plastic waste and releases hydrogen chloride gas and dioxins when heated above 200 degrees Celsius, posing serious risks to road construction workers and contaminating the bituminous mix. PVC identification and removal using near-infrared sorting equipment is standard practice in high-quality plastic road programs, and the MoRTH circular explicitly excludes PVC from acceptable plastic waste feedstocks. Similarly, plastics contaminated with pesticides, industrial chemicals, or medical waste must be excluded from the road construction waste stream.

4. Incorporation Methods

4.1 Dry Process

In the dry process, shredded plastic waste is added directly to the hot aggregate in the mix plant drum or pug mill before the addition of bitumen, coating the aggregate particles with a thin polymer film before bitumen binding. The process sequence is: heat aggregate to 165 to 170 degrees Celsius; add pre-shredded plastic at 8 to 10 percent by weight of bitumen (approximately 0.4 to 1.0 percent by weight of total mix); mix for 30 to 60 seconds to achieve uniform plastic coating of aggregate; add hot bitumen at 160 degrees Celsius and mix for a further 30 to 60 seconds; discharge and transport to site.

The dry process is simpler, requires less equipment modification, and is more amenable to on-site implementation at small to medium scale compared to the wet process. The plastic coating on aggregate particles modifies the aggregate surface chemistry, potentially improving adhesion with bitumen and reducing moisture-induced stripping. The method is particularly suitable for post-consumer mixed plastics that are difficult to blend uniformly with bitumen in a wet process, as the coating mechanism is less sensitive to plastic type and composition than the blending mechanism.

Professor Vasudevan's dry process method, which has been most extensively implemented in India, uses plastic waste at 8 percent by weight of bitumen, corresponding to approximately 1 tonne of plastic waste per kilometre of single-lane road construction using 50 mm thick wearing course. This plastic content is sufficient to achieve measurable improvements in mix performance while remaining within the workability constraints of conventional mix production and paving equipment. The process has been adopted by municipalities across Tamil Nadu, Karnataka, Andhra Pradesh, Maharashtra, and other states, with implementation on cumulative road lengths estimated in the tens of thousands of kilometres.

4.2 Wet Process

In the wet process, plastic waste is blended with bitumen at elevated temperatures (180 to 200 degrees Celsius) using high-shear mixing equipment to produce a homogeneous polymer-modified bitumen (PMB) before mixing with aggregate. The PMB is produced either at a central bitumen terminal or in a modified mix plant, and behaves as a modified binder with improved properties compared to unmodified penetration grade bitumen. The wet process requires specialized high-shear mixing equipment, precise temperature control, and

INTERNATIONAL JOURNAL OF ENGINEERING MANAGEMENT AND SOCIAL SCIENCES (IJEMSS)

e-ISSN : 3139-065X

www.ijemss.com

editor@ijemss.com

Vol. 01, Issue 5, May 2026, pp : 73-85

longer blending times (typically 1 to 2 hours) to achieve homogeneous dispersion of the polymer phase in the bitumen matrix.

The wet process produces more consistent and predictable bitumen modification than the dry process, as the polymer is uniformly distributed throughout the binder phase rather than concentrated at aggregate surfaces. This consistency is important for high-traffic roads and highway applications where performance reliability is critical and where the quality assurance requirements of conventional polymer-modified bitumen specifications must be met. Commercial PMB production using industrial-grade polymers (SBS, SBR) is well-established in India under MoRTH specifications, and the wet process for waste plastic modification is essentially an extension of this established technology using waste rather than virgin polymer feedstocks.

5. Effects on Bitumen Properties

5.1 Softening Point and Penetration

The softening point (ring and ball test) and penetration (needle penetration at 25 degrees Celsius) are the two most fundamental characterization tests for bitumen and its modifications. The softening point indicates the temperature at which bitumen softens sufficiently under load to cause pavement deformation — higher softening points indicate better high-temperature performance and rutting resistance. Penetration indicates stiffness at standard temperature — lower penetration indicates a harder, stiffer bitumen.

Published data from studies of plastic modification consistently demonstrate increases in softening point and reductions in penetration relative to the base bitumen. For LDPE modification at 4 to 12 percent by weight of bitumen, softening point increases of 4 to 16 degrees Celsius above VG-30 base bitumen (base softening point approximately 47 degrees Celsius) are reported, with penetration reductions of 15 to 35 percent. PP modification at 4 to 8 percent produces softening point increases of 8 to 18 degrees Celsius and penetration reductions of 25 to 45 percent. Mixed plastic waste modification at equivalent contents shows intermediate effects with greater variability, reflecting the inconsistency of mixed plastic feedstock composition.

5.2 Viscosity and Workability

The viscosity of plastic-modified bitumen at mixing and compaction temperatures (120 to 135 degrees Celsius) is higher than that of unmodified bitumen, reflecting the stiffening effect of the polymer network at elevated temperatures. This increased viscosity improves the coating of aggregate particles and the resistance of the bituminous mix to segregation during transport, but requires higher mixing and compaction temperatures (typically 5 to 15 degrees Celsius above those for unmodified bitumen) to achieve adequate workability and the target air void content of 3 to 5 percent in compacted specimens.

The increased compaction temperature requirement of plastic-modified mixes is a practical constraint on their use in climate conditions where the mix may cool below the workability threshold before compaction is completed, particularly for thin wearing courses on roads distant from the mix plant. Plant mix temperature monitoring, insulated truck bodies, and reduced haul distances mitigate this risk and are recommended in quality management plans for plastic road construction in hot climate conditions.

6. Mechanical Performance of Plastic-Modified Bituminous Concrete

6.1 Marshall Stability and Flow

The Marshall stability test — measuring the peak load resistance of a 101.6 mm diameter cylindrical specimen

INTERNATIONAL JOURNAL OF ENGINEERING MANAGEMENT AND SOCIAL SCIENCES (IJEMSS)

e-ISSN : 3139-065X

www.ijemss.com

editor@ijemss.com

Vol. 01, Issue 5, May 2026, pp : 73-85

at 60 degrees Celsius — is the standard mechanical performance indicator for bituminous concrete mixes in India and many other countries. The target Marshall stability for conventional BC Grade 1 wearing course under MoRTH specifications is a minimum of 9 kN, with a flow value (deformation at peak load) of 2 to 4 mm indicating a balance between stiffness and flexibility.

Research investigations of plastic-modified bituminous concrete consistently report Marshall stability improvements of 15 to 60 percent above plain bituminous concrete controls at optimal plastic content, with the improvement increasing with plastic content up to an optimum typically in the range of 6 to 12 percent plastic by weight of bitumen, beyond which stability may decline due to reduced binder coating of aggregates and increased brittleness. Representative data from published studies show Marshall stabilities of 12 to 18 kN for LDPE-modified mixes at 8 to 10 percent plastic content, compared to 9 to 12 kN for unmodified controls — improvements of 30 to 50 percent that substantially exceed the minimum specification requirement and provide margin for performance under challenging traffic and climate conditions.

6.2 Rutting Resistance

Rutting — the permanent longitudinal deformation of the pavement surface in wheel paths under repeated traffic loading — is the primary distress mode of bituminous pavements in hot climates including most of India. Rutting is caused by viscous flow of the bituminous binder at high pavement temperatures (surface temperatures in Indian conditions regularly exceed 60 degrees Celsius in summer) combined with densification of the mix under trafficking. Polymer modification of bitumen is the most effective strategy for improving rutting resistance, and plastic waste modification operates through the same fundamental mechanism.

Wheel tracking tests and repeated load permanent deformation tests on plastic-modified specimens consistently show rutting resistance improvements of 25 to 70 percent compared to unmodified controls. Dynamic creep tests at 60 degrees Celsius have demonstrated reductions in permanent strain accumulation of 30 to 60 percent for LDPE-modified mixes at 8 percent plastic content compared to VG-30 bitumen controls, indicating substantially improved resistance to the viscous flow mechanism that drives rutting. Field performance monitoring of plastic roads in Tamil Nadu and Karnataka has confirmed that plastic-modified road sections exhibit significantly less rutting than adjacent unmodified sections under equivalent traffic loading over periods of 3 to 8 years.

6.3 Indirect Tensile Strength and Fatigue

Indirect tensile strength (ITS), measured by the Brazilian splitting test on cylindrical specimens at 25 degrees Celsius, characterizes the tensile fracture resistance of bituminous concrete and its resistance to cracking under traffic-induced tensile stresses at the bottom of the bound layer. Plastic modification generally improves ITS values by 10 to 35 percent at optimal plastic content, reflecting the enhanced cohesion and tensile capacity of the stiffened binder.

Fatigue performance — the resistance of the bituminous mix to crack initiation and propagation under repeated tensile strain cycles — is more nuanced in its response to plastic modification. At moderate plastic contents (6 to 10 percent), fatigue life at intermediate strain levels is generally improved by 20 to 50 percent due to the enhanced cohesion and reduced binder susceptibility to repeated loading. At higher plastic contents, increased stiffness and reduced flexibility may reduce fatigue life at high strain levels, as the stiffer modified

INTERNATIONAL JOURNAL OF ENGINEERING MANAGEMENT AND SOCIAL SCIENCES (IJEMSS)

e-ISSN : 3139-065X

www.ijemss.com

editor@ijemss.com

Vol. 01, Issue 5, May 2026, pp : 73-85

mix becomes more brittle and less able to accommodate the tensile strains generated in thin pavements over weak subgrades. Optimal plastic content for a balance of rutting and fatigue performance is typically 6 to 10 percent by weight of bitumen.

6.4 Moisture Susceptibility and Stripping Resistance

Moisture damage — the deterioration of adhesion between bitumen and aggregate in the presence of water, leading to stripping of the binder film from aggregate surfaces and progressive disintegration of the pavement structure — is a major durability concern for bituminous pavements in Indian monsoon conditions. The tensile strength ratio (TSR), comparing ITS values of moisture-conditioned to unconditioned specimens, is the standard moisture susceptibility indicator under MoRTH specifications, with a minimum TSR of 0.80 required.

Plastic-modified bituminous concrete consistently shows improved TSR values of 0.85 to 0.95 compared to 0.75 to 0.85 for unmodified controls, reflecting the improved adhesion between modified bitumen and aggregate surfaces and the water-resistant character of polymer coatings. The improved stripping resistance of plastic-modified mixes is particularly valuable for roads in high-rainfall regions and for roads subject to waterlogging during monsoon seasons, where conventional bituminous surfaces frequently exhibit rapid moisture-induced deterioration. This durability advantage partially offsets the higher initial cost of plastic-modified mix production and contributes to the life cycle cost advantage of plastic roads over conventional alternatives.

7. Comparative Performance Data

Table 1 presents a comparative summary of mechanical performance improvements for different plastic types incorporated by the dry process at 8 percent by weight of bitumen in BC Grade 1 wearing course mix (60/70 penetration grade bitumen, MoRTH gradation):

Plastic Type	Softening Point Increase (°C)	Marshall Stability Gain (%)	Rutting Resistance Gain (%)	ITS Gain (%)	TSR Value	Workability
LDPE (carry bags)	+6 to +12	25-45%	30-55%	15-30%	0.87-0.93	Good
HDPE (bottles/containers)	+8 to +14	20-40%	35-60%	10-25%	0.85-0.92	Moderate
Polypropylene (PP)	+10 to +18	30-55%	40-65%	20-35%	0.86-0.94	Moderate
PET (bottles, coated agg.)	+4 to +10	15-35%	20-45%	10-20%	0.84-0.90	Good
Polystyrene (EPS)	+6 to +12	15-25%	25-40%	12-22%	0.85-0.91	Good
Mixed plastic waste	+4 to +12	15-40%	20-50%	10-25%	0.83-0.91	Variable
LDPE + PP blend (2:1)	+12 to +20	35-60%	45-70%	25-40%	0.88-0.95	Good

Table 1: Mechanical performance improvements for different plastic types at 8% by weight of bitumen (dry process)

INTERNATIONAL JOURNAL OF ENGINEERING MANAGEMENT AND SOCIAL SCIENCES (IJEMSS)

e-ISSN : 3139-065X

www.ijemss.com

editor@ijemss.com

Vol. 01, Issue 5, May 2026, pp : 73-85

Table 2 presents a comparison of plastic-modified bituminous concrete against conventional VG-30 bituminous concrete and commercial SBS polymer-modified bitumen (PMB 40) on key performance indicators:

Mix Type	Marshall Stability (kN)	Flow (mm)	Softening Point (°C)	Rutting Depth (mm/1000 cycles)	TSR	Cost Premium (%)
Plain BC (VG-30)	9.5-12.0	2.5-3.5	47-49	4.5-7.0	0.75-0.85	Baseline
Plastic modified (LDPE 8%)	13.0-17.0	2.5-3.5	53-59	2.5-4.5	0.87-0.93	3-8% less
Plastic modified (PP 6%)	14.0-18.5	2.0-3.0	55-63	2.0-4.0	0.86-0.94	2-6% less
Mixed plastic waste (8%)	12.0-16.0	2.5-4.0	51-57	2.8-5.0	0.83-0.91	2-7% less
Commercial PMB 40 (SBS)	15.0-20.0	2.0-3.5	60-68	1.5-3.5	0.88-0.95	15-25% more
LDPE + PP blend (2:1, 8%)	15.5-19.0	2.0-3.0	57-65	1.8-3.8	0.88-0.95	3-8% less

Table 2: Comparative performance of plastic-modified versus conventional and PMB bituminous concrete

8. Regulatory and Policy Framework in India

India has developed the most comprehensive national policy framework for plastic waste road construction of any country globally. The key regulatory and policy instruments include:

The Ministry of Road Transport and Highways (MoRTH) issued a circular in 2015 — subsequently updated and strengthened — mandating the use of plastic waste in road construction within 50 kilometres of cities with populations above 500,000. The circular specifies that plastic waste shall be used at a minimum content of 8 percent by weight of bitumen for wearing course construction, using the dry process method validated by the Central Road Research Institute (CRRI) and the specifications developed by NRRDA (National Rural Roads Development Agency).

The Plastic Waste Management Rules 2016, amended in 2018 and 2022, place extended producer responsibility obligations on plastic manufacturers and brand owners and identify road construction as a preferred end-of-life application for non-recyclable plastic waste. Urban local bodies are empowered to mandate plastic road construction within their jurisdictions and to create collection and pre-processing infrastructure for plastic feedstock supply.

The National Rural Roads Development Agency has incorporated plastic road specifications into the Pradhan Mantri Gram Sadak Yojana (PMGSY) rural road construction program, which has constructed over 750,000 kilometres of rural roads since its inception in 2000. The inclusion of plastic waste use in PMGSY specifications creates a massive potential demand for pre-processed plastic feedstock from rural and semi-urban communities, providing an economic incentive for plastic waste collection and pre-processing that extends beyond urban areas.

INTERNATIONAL JOURNAL OF ENGINEERING MANAGEMENT AND SOCIAL SCIENCES (IJEMSS)

www.ijemss.com

Vol. 01, Issue 5, May 2026, pp : 73-85

e-ISSN : 3139-065X

editor@ijemss.com

The Bureau of Indian Standards has developed IS 17452:2020 — Plastic Modified Bituminous Mixes: Specifications — providing standardized quality requirements for plastic-modified bituminous mixes produced by both dry and wet processes. The standard specifies acceptable plastic types (LDPE, HDPE, PP, and PS; PVC explicitly excluded), particle size requirements for shredded plastic, blending temperature ranges, and performance requirements for the finished mix including Marshall stability, flow, retained stability, and tensile strength ratio.

9. Global Case Studies and Field Performance

9.1 India: Tamil Nadu and Karnataka

Tamil Nadu is the birthplace of the Vasudevan dry process plastic road method, which was first implemented at Thiagarajar College of Engineering in Madurai in 2001 and subsequently scaled through a collaboration between the college and the Tamil Nadu government. By 2015, over 5,000 kilometres of roads in Tamil Nadu had been constructed or resurfaced using the plastic road method. Field performance monitoring of plastic roads in Tamil Nadu over periods of 8 to 15 years has consistently shown superior resistance to rutting, potholes, and moisture damage compared to adjacent conventional bituminous sections, with several sections showing minimal distress after periods during which equivalent conventional sections required multiple resurfacing treatments.

Karnataka, Andhra Pradesh, and Telangana have implemented plastic road construction at significant scale through both municipal urban road programs and state highway maintenance contracts. Bengaluru's Bruhat Bengaluru Mahanagara Palike has used plastic roads in multiple ward road renewal programs, targeting areas with both poor road condition and high plastic waste generation. The integration of plastic waste collection, segregation, and pre-processing into BBMP's solid waste management operations has created synergies between the waste management and road maintenance departments that have reduced both the cost of plastic road construction and the volume of plastic waste requiring landfill disposal.

9.2 Netherlands: PlasticRoad

The Netherlands-based PlasticRoad initiative, developed by engineering company KWS in partnership with Wavin and Total, takes a fundamentally different approach to plastic road construction than the Indian bitumen-modification method. Rather than incorporating plastic into bituminous mixes, PlasticRoad constructs road sections from prefabricated hollow modular sections manufactured from 100 percent recycled plastic, installed over a prepared sub-base as a structural road surface. The hollow interior of the modules provides space for utility cables and cables, and sensors embedded in the structure can monitor structural condition in real time.

A pilot section was installed in Zwolle in 2018 and has been monitored since installation. The system offers the advantage of complete factory prefabrication with predictable quality, rapid installation with minimal site disruption, full recyclability at end of life, and no bitumen requirement. Limitations include the higher initial cost compared to conventional asphalt, limited load-bearing capacity for heavy vehicle applications, and the challenge of managing thermal expansion and contraction of plastic road sections over the wide temperature range experienced in temperate climates.

9.3 Australia and South Africa

INTERNATIONAL JOURNAL OF ENGINEERING MANAGEMENT AND SOCIAL SCIENCES (IJEMSS)

e-ISSN : 3139-065X

www.ijemss.com

editor@ijemss.com

Vol. 01, Issue 5, May 2026, pp : 73-85

In Australia, several state road authorities including VicRoads and Transport for NSW have conducted trials of plastic-modified bituminous mixes using both virgin and waste polymer feedstocks, with post-consumer plastic waste trials focusing primarily on LDPE and mixed plastic from kerbside recycling collections. Repurpose It in Victoria has developed a certified process for incorporating glass, plastic, and rubber waste into road base and asphalt mix applications, with several council road projects completed in Melbourne and regional Victoria demonstrating equivalent or superior performance to conventional mixes.

South Africa's road research community has investigated plastic waste roads in the context of the country's acute plastic pollution problems and substantial road infrastructure investment needs. Research at the University of Pretoria and the Council for Scientific and Industrial Research (CSIR) has documented performance improvements consistent with global findings, and pilot road sections have been completed in Johannesburg and Cape Town. The cost reduction potential of plastic roads relative to conventional PMB is particularly significant in South Africa given the high cost of imported polymer modifiers and the abundance of plastic waste from informal settlements where formal recycling infrastructure is limited.

10. Environmental Considerations

10.1 Microplastic Release

A significant concern regarding plastic-modified road surfaces is the potential release of microplastic particles through pavement wear under traffic, weathering, and maintenance operations including sweeping and resurfacing. Tyre and road wear particles (TRWP) — fragments generated at the tyre-road interface by the abrasion and heat of rolling contact — are the largest source of microplastics in urban runoff globally, estimated at 0.5 to 1.0 million tonnes per year worldwide from rubber tyre material alone. Plastic road construction adds an additional potential source of plastic-derived wear particles, as plastic-modified wearing course material is exposed at the surface and subject to the same abrasion forces.

The magnitude of microplastic release from plastic roads relative to the plastic content incorporated is not yet well-characterized. Studies from India suggest that plastic concentrations in runoff from plastic-modified road sections are not significantly elevated compared to conventional asphalt under normal service conditions, because the plastic is encapsulated within the bituminous matrix and not exposed as free plastic particles at the surface. However, at road joints, edges, and areas of distress where the surface bituminous matrix has been disrupted, exposed plastic fragments can be mobilized by rainfall runoff. Long-term field monitoring studies quantifying microplastic emissions from plastic roads under realistic traffic and weathering conditions are a priority research need.

10.2 Toxic Emissions During Production

The pre-processing and incorporation of plastic waste in bituminous mixes at temperatures of 150 to 180 degrees Celsius generates volatile organic compounds (VOCs) and potentially toxic emissions that require careful management to protect the health of road construction workers and nearby residents. Studies of air quality at plastic road construction sites have identified elevated concentrations of benzene, toluene, ethylbenzene, and xylene (BTEX compounds) in the breathing zone above the paver, consistent with emissions from both the heated bitumen and the heating plastic feedstock. The concentrations measured in most studies are below occupational exposure limits when appropriate engineering controls — enclosed mixing plants, well-ventilated paving operations, respiratory protective equipment — are in place.

The exclusion of PVC from plastic feedstocks is essential to prevent dioxin and hydrogen chloride emissions

INTERNATIONAL JOURNAL OF ENGINEERING MANAGEMENT AND SOCIAL SCIENCES (IJEMSS)

e-ISSN : 3139-065X

www.ijemss.com

editor@ijemss.com

Vol. 01, Issue 5, May 2026, pp : 73-85

that would pose unacceptable health and environmental risks. Similarly, plastics contaminated with brominated flame retardants, pesticide packaging residues, or other hazardous chemical additives must be excluded, as these can generate highly toxic pyrolysis products at mixing temperatures. The quality control requirements for plastic feedstock screening and testing represent a non-trivial operational challenge for plastic road programs that must be addressed in program design and quality management plans.

10.3 Life Cycle Assessment

Life cycle assessment (LCA) studies comparing plastic road construction with conventional bituminous road construction must account for the avoided impact of plastic waste disposal (landfill or incineration), the reduced bitumen consumption, the changed production energy balance, and the extended service life attributed to improved mix performance. Several LCA studies of Indian plastic road construction have found net environmental benefits compared to conventional roads, driven primarily by the avoided landfill disposal impact of plastic waste and the reduction in virgin bitumen — a petroleum product with significant embodied energy and carbon.

A key uncertainty in plastic road LCA is the appropriate allocation of environmental impact between the road construction function and the plastic waste management function. Under a waste management perspective, plastic waste entering road construction has zero or negative environmental burden (it replaces disposal), producing a highly favorable LCA outcome. Under a materials perspective, using plastic waste in road construction may be less environmentally favorable than recycling it into higher-value products, depending on the comparison cases and scope boundaries. The absence of recycling market capacity for many non-recyclable plastic types in India means that in practice, the alternative to road construction use is landfill or open burning — against which plastic roads consistently show environmental advantages.

11. Challenges and Limitations

Despite compelling technical performance data and strong policy support in India, the widespread adoption of plastic waste road construction faces several significant challenges:

- Feedstock supply chain inconsistency: the reliable supply of pre-processed, quality-assured plastic waste feedstock at the volumes and specifications required for large-scale road construction programs requires organized collection, segregation, washing, and shredding infrastructure that is not yet systematically developed across most Indian cities and towns
- Quality variability of mixed plastic feedstocks: the heterogeneous composition of municipal plastic waste and the lack of systematic sorting in most collection systems produce feedstocks of variable composition that introduce inconsistency in bituminous mix performance, requiring more intensive quality control testing than conventional mixes
- Limited applicability to high-traffic roads: current Indian guidelines limit plastic-modified mixes to roads with traffic up to 30 million standard axles (MSA) cumulative design traffic, excluding major highways and expressways where higher performance standards and longer design lives are required and where commercial PMB specifications are mandated
- Scale gap between pilot projects and systematic implementation: most documented plastic road programs remain at the level of individual projects or municipal programs rather than state or national highway network scale, and the transition from pilot to systematic implementation requires procurement frameworks, supply chain development, and quality assurance systems that are not yet in place in most jurisdictions
- Worker health and safety management: the occupational health risks associated with plastic pre-processing, shredding, and high-temperature bituminous mix production require proper engineering controls, personal protective equipment, and health monitoring programs that increase operational complexity and cost compared to conventional road construction

INTERNATIONAL JOURNAL OF ENGINEERING MANAGEMENT AND SOCIAL SCIENCES (IJEMSS)

e-ISSN : 3139-065X

www.ijemss.com

editor@ijemss.com

Vol. 01, Issue 5, May 2026, pp : 73-85

- Long-term field performance data gaps: while several plastic road sections in Tamil Nadu and Karnataka have demonstrated good performance over 10 to 15 years, the global dataset of long-term field performance monitoring across different climates, traffic conditions, and plastic feedstock types is insufficient to confidently predict 20 to 30 year pavement design life performance

12. Future Research Directions

The following research priorities will be important in advancing the technical, environmental, and implementation dimensions of plastic waste road construction:

- Systematic long-term field performance monitoring of plastic road sections across diverse traffic, climate, and feedstock conditions in India and globally, with standardized distress survey protocols enabling cross-site comparison and design life calibration
- Quantification of microplastic release from plastic-modified road surfaces under realistic traffic and weathering conditions, including particle characterization and fate and transport modeling to assess environmental exposure
- Development of performance-based specifications for plastic-modified bituminous mixes calibrated to Indian traffic and climate conditions, moving beyond Marshall test criteria to include dynamic modulus, flow number, and fatigue test requirements consistent with mechanistic-empirical pavement design
- Investigation of optimal plastic-bitumen combinations and blend ratios, particularly for hybrid mixes combining waste LDPE and PP to achieve performance approaching commercial SBS PMB at substantially lower cost
- Research into high-plastic-content applications — road base stabilization, sub-base materials, drainage layers — that could utilize larger volumes of mixed plastic waste than surface course applications alone, expanding the waste utilization potential of road construction
- Development of certified pre-processing standards and supply chain traceability frameworks that ensure consistent feedstock quality and exclude hazardous plastic types, enabling the scaling of plastic road programs with confidence in product quality
- Economic modeling of integrated plastic waste collection, pre-processing, and road construction supply chains under different urban governance and financing models, identifying the institutional arrangements that make plastic roads financially viable without ongoing government subsidy

13. Conclusion

Plastic waste utilization in road construction represents one of the most pragmatic and technically validated circular economy applications available to the road construction sector today. The evidence base — spanning hundreds of laboratory studies, numerous field installations, and emerging long-term performance data — consistently demonstrates that plastic-modified bituminous concrete achieves Marshall stability improvements of 25 to 60 percent, rutting resistance improvements of 30 to 70 percent, and moisture resistance improvements of 10 to 20 percent compared to unmodified conventional mixes, while simultaneously diverting non-recyclable plastic waste from landfill and reducing net bitumen consumption.

India's position as the global pioneer and largest implementer of plastic road technology, backed by mandatory policy through MoRTH circulars and Plastic Waste Management Rules, and driven by the combined urgency of its plastic pollution crisis and road infrastructure deficit, makes it the most important test bed for the scalability and long-term performance of this technology. The field evidence from Tamil Nadu, Karnataka, and other states over periods of 8 to 15 years is broadly positive, confirming the fundamental validity of the technology and its suitability for Indian road construction conditions.

The challenges of feedstock supply chain development, quality consistency, worker health protection, and long-

INTERNATIONAL JOURNAL OF ENGINEERING MANAGEMENT AND SOCIAL SCIENCES (IJEMSS)

e-ISSN : 3139-065X

www.ijemss.com

editor@ijemss.com

Vol. 01, Issue 5, May 2026, pp : 73-85

term performance verification are real but addressable through systematic program design, quality management investment, and continued research. The comparative cost data in Table 2 demonstrate that plastic road construction can achieve performance approaching commercial PMB at 15 to 25 percent lower cost than PMB and at 3 to 8 percent lower cost than plain bituminous concrete, making it not just environmentally justified but economically advantageous for the road construction agencies and municipalities that implement it.

The transition from isolated pilot projects to systematic, quality-assured implementation at national scale — in India and in the many other countries where the combination of plastic waste volumes and road construction investment provides a compelling opportunity — requires the development of certified supply chains, performance-based specifications, procurement frameworks, and institutional capacity that can sustain plastic road programs beyond the enthusiasm of individual champions. Building this infrastructure for scale is the primary challenge and the primary opportunity in advancing plastic waste utilization in road construction from a promising technology to a mainstream practice.

References

1. Vasudevan, R., Sekar, A.R.C., Rajasekaran, S. & Vel Raj, B. (2012). Utilization of waste polymers for flexible pavement and easy disposal of waste polymers. Proceedings of the Institution of Civil Engineers: Waste and Resource Management, 165(2), 79-87.

2. Ministry of Road Transport and Highways (2015). Circular on Use of Waste Plastic in Road Construction. MoRTH, Government of India, New Delhi.

3. Bureau of Indian Standards (2020). IS 17452: Plastic Modified Bituminous Mixes: Specifications. BIS, New Delhi.

4. Central Road Research Institute (2013). Guidelines for Use of Plastic Waste in Hot Bituminous Mixes. CRRI, New Delhi.

5. Punith, V.S. & Veeraragavan, A. (2007). Behavior of asphalt concrete mixtures with reclaimed polyethylene as additive. Journal of Materials in Civil Engineering, 19(6), 500-507.

6. Moghaddam, T.B., Karim, M.R. & Abdelaziz, M. (2011). A review on fatigue and rutting performance of asphalt mixes. Scientific Research and Essays, 6(4), 670-682.

7. Sharma, B.M. et al. (2021). Plastic roads in India: A comprehensive review of technology, policy, and environmental considerations. Construction and Building Materials, 295, 123587.

8. Khurshid, M.B., Qureshi, N.A. & Hussain, A. (2015). Performance evaluation of polymer modified bituminous concrete. Arabian Journal for Science and Engineering, 40(12), 3537-3547.

9. PlasticRoad (2020). PlasticRoad Pilot Zwolle: Performance Monitoring Report Year 2. KWS Infra BV, the Netherlands.

10. Banerjee, A. (2014). Use of Waste Plastics in Bituminous Mix for Road Construction: Best Practices Manual. United States Agency for International Development / USAID, New Delhi.

11. Ingrassia, L.P., Lu, X., Ferrotti, G. & Canestrari, F. (2020). Renewable materials in asphalt mixes: Review. Construction and Building Materials, 261, 119908.

12. CPCB (2022). Annual Report on Plastic Waste Management in India. Central Pollution Control Board, Ministry of Environment, Forest and Climate Change, New Delhi.